ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice, dated 22nd—26th April 1937.

The attention of the public is invited to the Notification dated 21st April 1937, calling for tenders for "Constructing masonry reservoir and suction well, etc.," for water supply to Saklespur Town," published in pages 628-629, Part VI of the *Mysore Gazette*, dated 29th April 1937.

The last date of receiving tenders is fixed on 17th May 1937.

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the detailed notification inviting tenders for restoring Madagondanahalli Shettikere, Reg. No. 260 of Dodballapur Taluk published on pages 659-660 of Part VI of the *Mysore Gazette*, dated 6th May 1937. The last date for receipt of tenders is 2 P.M. on 24th May 1937 and the earnest money to accompany the tender is Rs. 250.

Notification dated 27th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th May 1937, for improving Primary Boys' School at Kengeri, Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and thirty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Primary Boys' School at Kengeri, Bangalore Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, after depositing an additional sum of Rs. 130 in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for improving Primary Boys' School at Kengeri, Bangalore Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
				Rs. a. p.		
1	Dismantling the existing Mangalore tiled roofing and stacking the released materials	Sqr.	15·9	0 7 0		
2	Dismantling walls and removing windows	S.ft.	409	0 0 3		
3	Burnt brick in mortar	C.ft.	1248	0 4 3		
4	Burnt stone jelly concrete in chunam mortar	"	9	0 3 9		
5	Burnt stone slabs 6" thick one line dressed and fixed in mortar ..	S.ft.	285	0 5 0		
6	Mysore teakwood doors with panelled shutters including painting ..	"	45	1 12 0		
7	(*a*) T.W. windows with iron bars panelled shutters, etc., including top R.C.C. ventilators 1½' high ..	"	112	1 14 0		
	(*b*) Do with top 1½' glazed ventilator	"	280	1 14 0		
8	Iron joists including conveying and fixing	Cwt.	31·23	10 8 0		
9	Jack arch terracing	Sqr.	11·2	38 0 0		
10	Ornamental parapet 9" thick and 1½' high as per design	S.ft.	179	1 0 0		
11	Chunam plastering	Sqr.	22.8	3 0 0		
12	Brick cornice 9" thick including plastering and white washing	R.ft.	182	0 8 0		
13	T.W. eve board 9" thick with silicate painting	"	128	0 5 6		
14	Cement pointing to basement ..	Sqr.	6.00	3 0 0		
15	White washing two coats	"	100.00	0 3 9		

Notification dated 1st May 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th May 1937, for constructing a Mosque at Kengeri, Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Mosque at Kengeri, Bangalore Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, after depositing an additional sum of Rs. 200 in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for constructing a mosque at Kengeri, Bangalore Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
				Rs. a. p.		
1	Earthwork excavating foundation and filling in basement with watering and consolidating	C.yd.	80	0 4 0		
2	Burnt stone jelly concrete in lime mortar 1 : 2 : 4 with tamping in layers not more than 4″ thick	C.ft.	631	0 3 6		
3	Size stone in lime mortar with bond stones 6 ft. apart in each course for foundation	,,	1,210	0 4 0		
4	Do bond stones 6 ft. apart in each course including all quoins neatly dressed 2″ wide for basement with face dressing ..	,,	331	0 4 6		
5	Burnt stone slabs 6″ thick two line dressed	S.ft.	341	0 6 0		
6	Do one line dressed ..	,,	268	0 5 0		
7	Burnt brick in lime mortar for superstructure	C.ft.	2,096	0 4 0		
8	Do for pillars and arch work	,,	250	0 5 0		
9	Wire cut brick in lime mortar ..	,,	225	0 9 0		
10	Burnt brick in mortar for towers' to minars including plastering and white washing	,,	108	0 6 0		
11	Burnt brick parapet wall 9″ thick 1¾′ high as per design including plastering and white washing	R.ft.	122	0 14 0		
12	Chunam mortar plastering to walls including rounding off all projecting receeding corners with cement mortar 1 : 4 for a width of 3″ ..	Sqr.	38.84	3 0 0		
13	White washing two coats	,,	38.84	0 4 0		
14	Pointing to masonry with snowcrete 1 : 3 cement to sand and lining for basement	,,	2.10	4 0 0		
15	Cement perforated pannels, as per design, 1½″ thick, with 2″ thick and 2″ wide border alround 1 per cent reinforcement neatly finished with splayed front beads in relief ..	S.ft.	139	1 0 0		
16	Rolled steel girders as per B.S.S. including lifting, hoisting and boxing with terrace bricks in cement mortar, reinforced with galvanised steel-texnet tied alround with one coat of anti-corrosive paint and fixing with cement concrete in walls ..	Cwt.	36	10 0 0		

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in Figures	Rate quoted in Words
				Rs. a p.		
17	Block cornice 9″ depth 3″ projection as per design	R.ft.	147	0 8 0		
18	Flooring with cement concrete 1 : 2 : 4 1½″ thickon 6″ Burnt stone jelly in lime concrete with topping of red cement ¼″ thick finished with vionite 2½ lbs. per sqr. and cut to the required tile pattern	Sqr.	8.70	25 0 0		
19	Reinforced cement concrete roofing 1 : 2 : 4—6″ thick with expansion joints wherever necessary and ceiling plastered with finely ground lime mortar as per design with covering and off sets and with surki concrete 4″ thick with two coats of flat tiles plastered smooth	..	..	..		
20	Skirting of 1″ thick cement concrete 1 : 2 : 4 with topping of ¼″ thick 9″ high as per design for interior walls	R.ft.	184	0 1 0		
21	Zinc rain water spouts of 4″ sqr. and 2½′ long	Each	10	1 2 0		
	Central Dome.					
1	Burnt brick in lime mortar	R.ft.	263	0 4 6		
2	Rolled steel girders 4″×1¾″ including painting	Cwt.	1.50	10 8 0		
3	Reinforced cement concrete dome of 9″ thick with steel ribs and channels at bottom with plastering, etc., complete on both sides including white washing	Sqr.	1.65	100 0 0		
4	R.C.C. roofing with plate glass at centre	,,	0.74	50 0 0		
5	Architrove at the top of octogon ..	R.ft.	30	0 8 0		
6	Chunam mortar plastering ¾″ thick ..	Sqr.	4.66	3 2 0		
7	White washing two coats	,,	4.66	0 4 6		

M. K. NARASIMHA IYER,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated the 30th April 1937.

EXTENSION OF MATERNITY HOSPITAL BUILDING AT SHIMOGA.

The attention of the public is hereby invited to the notification in pages 661-663 of the *Mysore Gazette*, dated 6th May 1937, calling for tenders for the extension of the Maternity Hospital Building at Shimoga.

Each tender must be accompanied by a treasury chellan for having deposited Rs. 480 as earnest money.

The last date for receiving tenders is 3 P.M. on Friday the 21st May 1937.

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 29th April 1937.

The attention of the public is invited to the notification published in pages 663-667 of the *Mysore Gazette*, dated 6th May 1937, calling for tenders for the constructions of Cooly-quarters, Senior Operators' Quarters both at Chikmagalur and Tarikere, respectively.

The last date of receipt of tender in this office is 17th May 1937.

Notification dated 29th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th May 1937, for constructing Senior Operator's Quarters at Tarikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Senior Operator's Quarters at Tarikere in default of which tenders will be rejected. Applications or representations to adjust earnest money out of any pending bills will not be considered.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due coursy. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Senior Operator's Quarters at Tarikere.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation and filling in	C.yd.	0 4 6	67	19
2	Stone jelly concrete in mortar	C.ft.	0 5 0	596	186
3	Stone in clay for foundation and basement ..	C.ft.	0 4 0	1,390	348
4	Burnt brick in clay for superstructure ..	,,	0 4 0	2,399	600
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 12 0	234	175
6	Pointing with cement mortar	Sqr.	5 0 0	2·03	10
7	Plastering with chunam mortar	,,	4 6 0	46·39	203
8	White washing and colour washing 2 coats ..	,,	0 4 6	48·42	14
9	Flooring with 1½" cement concrete on a bed of 3" lime concrete including cement plastering ½" thick	,,	20 0 0	8·09	162
10	Roofing with 1st class Mangalore Tiles on teak reepers including 2 coats of wood-oiling, etc., complete	,,	32 0 0	15·49	496

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
11	Ridge tiles set in mortar	R.ft.	0 14 0	69	60
12	Teakwood wrought and put up including 2 coats of wood oiling	C.ft.	5 0 0	73·33	367
13	Doors with teakwood frame and battened shutters 1" thick including fixing, etc., complete	S.ft.	1 12 0	163	285
14	Plain teakwood eave board 1"×9" thick including fixing, etc., complete	R.ft.	0 9 0	150	84
15	Windows with teakwood frame battened shutters 1" thick with iron bars, etc., complete	S.ft.	2 0 0	110	220
16	Teakwood shelves with battened shutters ..	„	1 0 0	48	48
17	Expanded metal 3½"×1½" with ⅛ shutters with Teakwood frame work fixed, etc., compete	„	0 12 0	94	71
18	Silver grey paint 2 coats	Sqr.	3 8 0	11·58	40
19	Ventilating tiles	Each	1 0 0	8	8
20	Constructing sinks	„	4 0 0	2	8
21	Stone mortar and pestle	„	5 0 0	1	5
22	Chunam Border	R.ft.	0 4 0	51	13
23	Providing and fixing out let pipes :—				
	(*a*) 2" diameter	Each	1 4 0	2	3
	(*b*) 1½" do	„	1 0 0	4	4
24	Levelling ground	C.yd.	0 4 0	121	30
25	Providing and fixing finials	Each	1 8 0	9	14
26	Constructing Ovan in Bath Room including cost of Handa	L. S.	..	..	30
27	Constructing drain and soakage pits ..	„	..	..	50
28	Providing and fixing wall planks including pegs, etc., complete	„	..	..	30
29	Unforeseen and sundry charges	„	..	..	71
30	Cost of constructing one latrine as per detailed estimate enclosed	„	(as per detailed below.)		160
31	R.C. perforated ventilators	S.ft.	1 4 0	51	64
	Total ..				3,880
	Contingencies at 5 per cent				194
	Grand Total ..				4,074
	Abstract for Latrine.				
1	Earthwork excavation	C.yd.	4 6 0	4	1
2	(*a*) Stone in mortar foundation and basement ..	C.ft.	0 4 6	130	37
	(*b*) Burnt brick in mortar superstructure ..	C.ft.	0 5 0	193	60
	(*c*) Chunam plastering	Sqr.	4 0 0	4·91	20
	(*d*) Cement pointing	„	5 0 0	0·56	3
	(*e*) White and colour washing 2 coats ..	„	0 4 6	5·47	2
	(*f*) Cement plastering ½" thick	„	10 0 0	80	8
	(*g*) Tar washing 2 coats	„	2 8 0	0·63	2
3	Flooring with 3" concrete and 1½" cement concrete and plaster ½" thick in cement ..	„	20 0 0	0·38	8
4	Fixing outlets constructing drain	No.	8 0 0	1	8
5	Providing galvanized iron sheet tubs 12"×6", complete with tarring	„	0 12 0	6	5
	Total ..				154
	Contingencies ..				6
	Grand Total ..				160

Notification dated 29th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th May 1937, for constructing Senior Operators' Quarters at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 200 (two hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Senior Operators' Quarters at Chikmagalur, in default of which tenders will be rejected. Applications or representations to adjust earnest money out of any pending bills will not be considered.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Senior Operator's Quarters at Chikmagalur.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation and filling in	C.yd.	0 4 6	67	19
2	Stone jelly concrete in mortar	C.ft.	0 4 6	596	168
3	Stone in clay for foundation and basement	C.ft.	0 4 0	1,390	348
4	Burnt brick in clay for superstructure	„	0 4 0	2,399	600
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	0 14 0	234	205
6	Pointing with cement mortar	Sqr.	5 0 0	2.03	10
7	Plastering with chunam mortar	„	4 6 0	46.39	203
8	White washing and colour washing 2 coats	„	0 4 6	48.42	14
9	Flooring with 1½" cement concrete on a bed of 3" lime concrete includng cement plasterng 1½" thick	„	20 0 0	8.09	162
10	Roofing with 1st class Mangalore Tiles on teak reepers including 2 coats of wood oiling, etc., complete	„	28 0 0	15.49	434
11	Ridge tiles set in mortar	R.ft.	0 12 0	69	52
12	Teakwood wrought and put up including 2 coats of wood oiling	C.ft.	5 0 0	73.33	367
13	Doors with teakwood frame and battened shutters 1" thick including fixing, etc., complete	S.ft.	1 12 0	163	285
14	Plain teakwood eave board 1"×9" thick including fixing, etc., complete	R.ft.	0 8 0	150	75

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
15	Windows with teakwood frame battened shutters 1" thick with iron bars, etc., complete ..	S.ft.	2 0 0	110	220
16	Teakwood shelves with battened shutters ..	,,	1 0 0	48	48
17	Expanded metal $3\frac{1}{2}" \times 1\frac{1}{2}"$ with $\frac{1}{8}$ shutters with Teakwood frame work fixed, etc., complete	,,	1 0 0	94	94
18	Silver grey paint 2 coats	Sqr.	3 8 0	11.58	40
19	Ventilating tiles	Each	1 0 0	8	8
20	Constructing sinks	,,	4 0 0	2	8
21	Stone mortar and pestle	,,	5 0 0	1	5
22	Chunam Boarder	R.ft.	0 4 0	51	13
23	Providing and fixing outlet pipes :—				
	(*a*) 2" diameter	Each	1 4 0	2	3
	(*b*) $1\frac{1}{2}"$ do	,,	1 0 0	4	4
24	Levelling ground	C.yd.	0 4 0	121	30
25	Providing and fixing finials	Each.	1 8 0	9	14
26	Constructing Ovan in Bath Room including cost of Handa	L. S.	..	..	30
27	Constructing drain and soakage pitss	,,	..	..	50
28	Providing and fixing wall planks including pegs, etc., complete	,,	..	..	30
29	Unforseen and sundry charges	,,	..	..	70
30	Cost of constructing one latrine as per detailed estimate conclosed	L. S.	(as per details below)		160
31	R. C. perforated ventilators	S.ft.	1 4 0	51	64
	Total ..				3,833
	Contingencies ..				167
	Grand Total ..				4,000
	Abstract for Latrine.				
1	Earthwork excavation	C.yd.	0 4 6	4	1
2	(*a*) Stone in mortar foundaton and basement ..	C.ft.	0 4 6	130	37
	(*b*) Burnt brick in mortar Superstructure ..	C.ft.	0 5 0	193	60
	(*c*) Chunam plastering	Sqr.	4 0 0	4.91	20
	(*d*) Cement pointing	,,	5 0 0	0.56	3
	(*e*) White and colour washing 2 coats ..	,,	0 4 6	5.47	2
	(*f*) Cement plastering $\frac{1}{2}"$ thick	,,	10 0 0	0.80	8
	(*g*) Tar washing 2 coats	,,	2 8 0	0.63	2
3	Flooring with 3" concrete and $1\frac{1}{2}"$ cement concrete and plaster $\frac{1}{2}"$ thick in cement ..	,,	20 0 0	0.38	8
4	Fixing outlets constructing drain	No.	8 0 0	1	8
5	Providing galvanized iron sheet tubs 12 ×6", complete with tarring	,,	0 12 0	6	5
	Total ..				154
	Contingencies				6
	Grand Total ..				160

IRWIN CANAL DIVISION, MANDYA.

Abstract Notification dated 5th May 1937.

The attention of the public is invited to the notification published in page 641, Part VI of the *Mysore Gazette*, dated 29th April 1937, regarding auction sale of buildings at Hulikere, Mandya Taluk. Auction will be conducted at 11 A.M. on 24th May 1937.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 7th May 1937.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 1st June 1937, for the work of providing sanitary fittings with drainage arrangements to the Inspection Lodge at Sivasamudram. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 60 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for the work of providing sanitary fittings with drainage arrangements to the Inspection Lodge at Sivasamudram," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Approximate estimate of quantities for the work of providing sanitary fittings with drainage arrangement to the Inspection Lodge at Sivasamudram.

No.	Particulars	Unit	Quantity
	Soil and waste connections.		
1	Providing 4" C. I. soil pipe with specials such as bends, offsets and junctions, etc., laying and jointing with lead complete	R.ft.	64
2	Do 3" waste pipe do	"	12
3	Providing and fixing 4" W.I. pipe for vent including providing and laying 4" C.I. soil pipe with specials from the nearest manhole providing and fixing 4 zinc ornamental cowl supports, etc.	No.	2
4	Fixing water closet and lavatory set complete	"	8

No.	Particulars	Unit	Quantity
5	Fixing accessories	No.	4
6	Painting white enamel to all C.I. and pipe fittings	"	8
7	Painting vent pipe	"	2
8	Constructing ground sink with cement concrete and cement plastering	"	4
9	Constructing ordinary cistern in cement mortar providing and fixing 6" dia. grating	"	4
10	Wall bore and redoing in lime mortar	"	8
11	Providing and laying 1½" galvanised pipe with fittings laying and jointing, groving and redoing complete	R.ft.	24
12	Cornice bore and redoing in lime mortar	No.	2
13	Providing 1¼" lead pipe bending and fixing and making lead wiped solder joints	"	4
14	Do ¾" and ½" do	"	12
15	Providing and fixing ½" Nickel plated stop cocks	"	8
16	Do bib cocks	"	4
17	Providing white glazed tiles over lavatory basin with cement mortar	S.ft.	14
18	Water connection with ¾" galvanised pipe with fittings laying and jointing wall bore, wall groving and redoing complete from outside bath room	Each connection	8
	Drainage arrangements.		
1	Providing 4" S.W. pipe laying and jointing in cement mortar earthwork excavation and refilling, watering and tamping and carting surplus earth complete	R.ft.	440
2	Providing 6"×4" S.W. gully trap with grating, constructing cistern in cement mortar and fixing of trap complete	No.	4
3	Providing and fixing 12"×9" C.I. hinged lid and frame	"	4
4	Constructing manhole 3' diar. inside with 9" concrete bed, brick in mortar 9" thick wall, cement plastering making drain and providing and fixing 21" diar. C.I. manhole cover and frame complete	"	7
5	Constructing septic tank 6'×4'×6' below inlet with inlet and outlet connections 1' lime mortar concrete bed, brick in mortar 9" thick wall, cement plastering, covering slab 5" to 6" thick providing and fixing 21" dia. C.I. manhole cover and frame complete	"	1

SYED AHMED HUSSAIN,
For *Sanitary Engineer.*

MEDICAL DEPARTMENT

OFFICE OF THE SUPERINTENDENT, GOVERNMENT MEDICAL STORES, BANGALORE CITY.

Abstract Notification dated 18th March 1937.

The attention of the public is invited to the detailed notification, published in pages 631-632 of Part VI of the *Mysore Gazette*, dated 29th April 1937, regarding the auction sale of unserviceable articles of the Medical Stores, Bangalore.

The date of sale of the articles fixed for Wednesday the 5th May 1937 has been altered to Thursday the 27th May 1937.

M. HIRANYAIYA,
Superintendent